



HVAC SYSTEM REPLACEMENT PROPOSAL

COMPANY CREDENTIALS & QUALIFICATIONS

Professional Certifications & Licensing

- Licensed HVAC Contractor - State of Georgia | South Carolina | North Carolina
- EPA Section 608 Universal Certification - All technicians certified
- Fully Licensed, Bonded, and Insured
- Commercial HVAC experience serving municipal and institutional facilities

Insurance Coverage

- General Liability Insurance: \$1,000,000 per occurrence / \$2,000,000 aggregate
- Workers Compensation Insurance: Full coverage for all employees
- Commercial Auto Insurance: All company vehicles covered
- Certificates of Insurance available upon request

Safety & Compliance

- OSHA-compliant safety protocols for all jobsites
- Background-checked technicians suitable for public facilities
- Drug-free workplace policy
- Safety meetings and training conducted regularly
- Specialized protocols for occupied building operations

Commercial Experience

- Municipal buildings and government facilities
- Educational institutions and libraries
- Commercial office buildings
- Multi-unit residential properties
- Experience with large tonnage commercial systems



Project:	McDuffie County Library
Location:	Augusta, Georgia 30909
System Capacity:	30 Tons Total Cooling Capacity
Proposal Date:	December 26, 2025
Prepared For:	McDuffie County Administration

SCOPE OF WORK

Giesbrecht HVAC proposes to furnish all labor, materials, and equipment necessary to remove and replace the existing HVAC system at the McDuffie County Library with a new, high-efficiency 30-ton commercial cooling system with hot water heating capability.

- Complete removal and disposal of existing HVAC equipment
- Installation of new outdoor condensing units and indoor air handling unit
- Connect refrigerant piping with appropriate accessories for extended line sets
- Connect to low-voltage control wiring throughout. Upgrade where needed.
- System startup, commissioning, and performance verification
- Owner training on system operation

EQUIPMENT SPECIFICATIONS

Outdoor Condensing Units (Quantity: 2)

Carrier Model 38AXZM16A0A5

- 15-ton capacity per unit (30 tons total)
- Two-stage cooling with single circuit design
- 208/230V, 3-phase, 60Hz electrical
- Aluminum/copper condenser coil for durability
- Factory-installed electro-mechanical controls
- Hail guard protection included
- Low ambient operation kit for year-round cooling capability
- Solenoid valves for extended refrigerant line applications

Indoor Air Handling Unit (Quantity: 1)

Carrier Model 40RLAA30T2A5

- 30-ton capacity, dual circuit configuration
- R-454B refrigerant (next-generation, low-GWP)
- 208/230V, 3-phase, 60Hz electrical
- Direct expansion cooling coil with aluminum/copper construction
- Two-row hot water heating coil for supplemental heat
- Variable frequency drive (VFD) for energy-efficient fan operation
- Medium static pressure fan configuration



-
- Electromechanical unit controls

Controls and Thermostat

- Carrier Connect Wi-Fi enabled thermostat
- 4.3-inch color touchscreen display
- Remote monitoring and adjustment capability
- Programmable scheduling for energy management

INVESTMENT

Description	Amount
Complete HVAC System Replacement as specified above, including all equipment, labor, materials, and installation	\$85,089
PROJECT INVESTMENT	\$85,089
Discount for Signing as part of Current Project	-\$3000
Actual Project Investment if Signed by January 9, 2025	\$82,089

WARRANTY COVERAGE

Outdoor Condensing Units

- Standard manufacturer's 1-year parts warranty
- Extended 5-year parts-only warranty included

Indoor Air Handling Unit

- Standard manufacturer's 1-year parts warranty
- Extended parts warranty available (Years 2-5)

Labor Warranty

- Giesbrecht HVAC provides a 1-year labor warranty on all installation work

INSTALLATION DETAILS

- Work to be performed during normal business hours unless otherwise arranged
- Coordination with facility management to minimize disruption to library operations
- All work performed by licensed, insured technicians
- Jobsite kept clean and debris removed daily
- Final inspection and system commissioning upon completion
- Complete documentation package provided including equipment manuals and warranty certificates



EXCLUSIONS

The following items are not included in this proposal unless specifically noted:

- Electrical service upgrades or modifications to main electrical panel
- Structural modifications or roof penetrations beyond equipment mounting
- Boiler or hot water system work
- Building automation system (BAS) integration
- Asbestos abatement or hazardous material handling

TERMS AND CONDITIONS

Proposal Validity

This proposal is valid for 30 days from date of issue.

Estimated Timeline

Equipment lead time is approximately 4-6 weeks from order. Installation duration estimated at 5-7 working days.

Insurance

Giesbrecht HVAC maintains full general liability and workers' compensation insurance. Certificates available upon request.

Payment Methods Accepted

- Check (payable to Giesbrecht HVAC)
- ACH/Wire Transfer
- Credit Card (Visa, MasterCard, American Express) 3.5% Fee Applies

Payment Terms

- Invoices are due upon receipt unless Net 30 terms are pre-approved
- Late payments subject to 1.5% monthly finance charge
- Change orders require written approval and will be invoiced separately
- All payments apply to oldest outstanding invoices first

Contract Terms

- Proposal valid for 30 days from date of submission
- Pricing subject to change after validity period
- Signed proposal constitutes a binding contract
- Work will commence upon receipt of deposit and signed contract



ACCEPTANCE

By signing below, the parties agree to the scope of work, terms, and conditions outlined in this proposal.

GIESBRECHT HVAC

McDUFFIE COUNTY

Chandler Giesbrecht, Owner

Authorized Representative

Date

Date

GIESBRECHT HVAC

Professional Heating & Cooling Solutions

Licensed in Georgia, South Carolina, and North Carolina